NEWTOWN URBAN CONSERVATION STUDY. - 'C' CITATIONS. Ref: 246

Richard Peterson Architect & Conservation Consultant. 1997.

NAME:

ADDRESS: 10 Virginia Street

USE: House

SIGNIFICANT DATE:

· CONSTRUCTION DATE: 1917 SOURCE: 1

DESIGNER: — <u>BUILDER</u>:

CRITERIA: H1; Ar1

HISTORIC THEME: 2.3

DESCRIPTION:

STYLE: Edwardian STORIES: 1

STORIES: 1 D

DETACHED.

MATERIALS:

WALLS Timber

ROOF Colorbond

STRUCTURE Stud

CONDITION: Good

INTACTNESS: Very good

THREATS: —

SIGNIFICANT INTACT ELEMENTS:

FORM. FACADE. VERANDAH. ROOF FORM. GABLE DECORATION. VERANDAH

DECORATION. CHIMNEYS. Pots. WINDOWS. GARDEN STRUCTURE. Arbour. CONTEXT

Nos: 11, 12, 13 & 14.

SIGNIFICANCE:

TYPE:

HISTORICAL. ARCHITECTURAL.

LEVEL:

LOCAL.

DESIGNATION EXISTING:

PLANNING SCHEME.

RECOMMENDED CONTROL:


PLANNING SCHEME.

OBSCURED.

SURVEY: RP

DATE:29.3.1997

NEGS: 10.12 & 1281.5,6&11



urgnia street

801 No 10. No 12 sebore I

RP. 29.3.97 NTS.

HISTORY: Arthur Madey owned fenced land measuring 45' in 1916 and built a timber house on the following year. He sold it to William Barnet, a clerk, the same year. Barnet was still living there in 1925. 1

VISUAL DESCRIPTION: A triple-fronted almost square timber Edwardian house with a high-hipped roof. The left and rear right side bays are set forward as gables. Upper gables are timbered and jetty on convex timber brackets. Below are mock shingles, timbered over a mould. There are ripple-iron hipped window hoods on large ogee fretwork brackets.

Windows are pairs. The verandah returns around the angle under the hip at right breakpitch. At the angle on splay is a three-sash rectangular bay window. The verandah has plain posts with very unusual Art Nouveau fretwork brackets. The entrance has side and fan-lights. The plain brick chimney has a top mould and a tall terracotta pot. There is a metal pipe arbour at the pedestrian gate with climbing roses, contemporary with the house and brick edging to the serpentine path.

SIGNIFICANCE: A characteristic triple-fronted timber Edwardian house with interesting details such as the verandah brackets and contextual elements such as the arbour, built in 1917. It is architecturally significant locally as representative of this variant of an Edwardian house, and historically in embodying life in Newtown during the Great War and as evidence of the continuing building industry in this period.

INTACTNESS: Very good. The verandah floor has been replaced with a concrete slab and the fence is not appropriate.

CONDITIONS & THREATS: Good.

¹ City of Newtown and Chilwell Ratebooks.